DISTRICT NIRMITHI KENDRA, CIVIL STATION, MALAPPURAM.

Ph: 0483- 2735594

INVITATION OF TENDER (LABOUR)

Tender No : DNKMLP/TENDER/LBR/ P1/ 59/2026-A1			**22/10/2026**
PROJECT NAME	**CONSTRUCTION OF NEW BUILDING FOR JANAKEEYA AROGYA KENDRAM AT PARATHAKKAD UNDER FHC OMANOOR IN CHEEKKODE GRAMA PANCHAYATH**		
LOCATION	**Parathakkad**	**Taluk :**	**Kondotty**
SCOPE OF WORK			

Tenders are invited from reputed firms/Labour suppliers for the specified works (schedule attached) as item rate contract.

Tender form and Tender schedule may be downloaded from District administrative website - **www.nirmithikendramlp.com** , Tenders should have addressed to , **Project Manager cum Exe.secretary, District Nirmithi Kendra, Civil Station, Malappuram, 676505, phone : 0483-2735594. Tenders are accepted through registerd post/Courier/by hand.** Late tenders will not be accepted. Tenders will be opened in the presence of Tenderer or their authorized representatives who may be present on that time. If the Tender opening date happens to be a declared holiday, the process will be done on the next working day at same time and place. Further details can be had from the office of District Nirmithi Kendra, Civil Station, Malappuram during working hours.

1	**Last Date & Time of Submission of Bids**	**:**	**30.10.2026, 3.00 pm**
2	**Date & Time of Opening of Bids**	**:**	**31.10.2026, 3.00 pm**
3	**Bid validity**	**:**	**60 days**

Name :

Address of firm :

Signature :

Project manager cum Exe.secretary
District Nirmithi Kendra, Malappuram.

Signature :

22/10/26
Project Manager cum
Executive Secretary
District Nirmithi Kendra
Civil Station, Malappuram

DISTRICT NIRMITHI KENDRA
MALAPPURAM

INSTRUCTIONS TO BIDDERS

Tender No : DNKMLP/TENDER/LBR/ P1/ 59/2026-A1	22/10/2026
Project Name	CONSTRUCTION OF NEW BUILDING FOR JANAKEEYA AROGYA KENDRAM AT PARATHAKKAD UNDER FHC OMANOOR IN CHEEKKODE GRAMA PANCHAYATH

1. The cover containing the tender should be superscribed as " **Tender for labour work of ".....**".
2. The rates should be quoted in the specified schedule itself.
3. The work should be completed within **120 days** from the date of receipt of work order.
4. All materials will be provided seperatly as per site requirement in time. Nails, Scaffolding ,Shuttering materials, vibrators, mixer machines, lifts and all other machineries etc.. , if needed should be provided by the labour/mason.
5. **Work should be carried out with at most care and quality as directed by the site in charge and should be completed with in the proposed completion period.**
6. Penalty @ 1 % per week will be imposed for any delay in completing works, after **120 days** of work order subject to a maximum of 10%.
7. Part payments against the progress of work will be released by Nirmithi kendra depending on assessment of the progress of work.
8. All statutory payments towards the welfare of labours engaged will be the sole responsibility of the Labour contractor
9. **The undersigned reserves the right to reject any or all tenders without assigning any reasons.**Tenders not satisfying the above Terms and conditions are liable to be rejected without any further communication.
10. **No employee of DNKM, personally or through family members, will in connection with the tender/Quotation for, or the execution of a contract, demand, take a promise for or accept, for self or third person, any material or immaterial benefit which the person is not legally entitled to.**

Name :
Address of firm :
Signature :

Project manager cum Exe.secretary
District Nirmithi Kendra, Malappuram
Signature :

22/10/26

Project Manager Cum Executive Secretary District Nirmithi Kendra Civil Station, Malappuram

DISTRICT NIRMITHI KENDRA 22 OCT MALAPPURAM

TENDER SCHEDULE - LABOUR

(FORMAT FOR QUOTING UNIT PRICE OF LABOUR)

DATE : 22/10/2026

Tender No : DNKMLP/TENDER/LBR/ P1/ 59/2026-A1

Project Name : CONSTRUCTION OF NEW BUILDING FOR JANAKEEYA AROGYA KENDRAM AT PARATHAKKAD UNDER FHC OMANOOR IN CHEEKKODE GRAMA PANCHAYATH

Sl no	Details of labour work	Quantity	unit	Rate per unit (without GST)	unit
	APPENDIX - A (Concrete works, Masonry works, Plastering works)				
1	2.8.1 - Labour charge for Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or *drains (not exceeding 1.5 m in width or 10 sqm on plan), including* dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil	**1.000**	cum	**Rs**	**cum**
2	60.7.1 - Labour charge for DRY RUBBLE MASONRY _ Dry rubble without concrete levelling course masonry with good quality blasted rubble including packing to compactness to lines and levels cost and conveyance of all materials labour charges etc. complete as per direction of Departmental officers at site	**1.000**	cum	**Rs**	**cum**
3	50.2.25.1- Labour charge for Filling with contractor's own earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m as per direction of site Engineer-in-charge	**1.000**	cum	**Rs**	**cum**
4	4.1.8- Labour charge for laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	**1.000**	cum	**Rs**	**cum**
5	5.1.2 - Labour charge for Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:1:5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size derived from natural sources)	**1.000**	cum	**Rs**	cum
6	5.2.2 - Labour charge for Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up tot floor five level excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3(1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	**1.000**	cum	**Rs**	cum
7	5.3 - Labour charge for Reinforced cement concrete work in beams, suspended floors, roofs, having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level excluding the cost of centering, shuttering, finishing and reinforcement, with1:1.5:3 (1 cement : 1.5 coarse sand (Zone III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources)	**1.000**	cum	**Rs**	cum

8	5.1.3 - Labour charge for laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	1.000	cum	Rs	cum
9	5.9.1 - Labour charge for Centering and shuttering including strutting, etc. and removal of form for:Foundations, footings, bases of columns, etc for mass concrete	1.000	sqm	Rs	sqm
10	5.9.16.1- Labour charge for Centering and shuttering including strutting, etc. and removal of form for: Edges of slabs and breaks in floors and wallsUnder 20 cm wide	1.000	metre	Rs	metre
11	5.9.3 - Labour charge for Centering and shuttering including strutting, etc. and removal of form for:Suspended floors, roofs, landings, balconies and access platform	1.000	sqm	Rs	sqm
12	5.9.5 - Labour charge for Centering and shuttering including strutting, etc. and removal of form for:Lintels, beams, plinth beams, girders bressumers and cantilevers	1.000	sqm	Rs	sqm
13	5.9.6 - Labour charge for Centering and shuttering including strutting, etc. and removal of form for:Columns, Pillars, Piers, Abutments, Posts and Struts	1.000	sqm	Rs	sqm
14	5.22.6- Labour charge for Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth levelThermo - Mechanically Treated bars of grade Fe-500D or more	1.000	kg	Rs	kg
15	5.22A.6- Labour charge for Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete above plinth level.Thermo - Mechanically Treated bars of grade Fe-500D or more	1.000	kg	Rs	kg
16	50.6.2.2 - Labour charge for Solid masonry using pre cast solid blocks (factory made) of size 30x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for super structure up to floor two level with thickness 15cm in : CM 1:6 (1 cement : 6 coarse sand) etc complete	1.000	cum	Rs	cum
17	50.6.2.1 - Labour charge for Solid block masonry using pre cast solid blocks (Factory made) of size 30x20x15 cm or nearest available size confirming to IS 2185 part I of 1979 for foundation and plinth with thickness 15cm in: CM 1:6 (1 cement :6 coarse sand) etc complete	1.000	cum	Rs	cum
18	OD21363/2026-2027 - Labour charge for fixing pressed steel door frames manufactured from commercial Tata Galvano steel sheet 1.60 mm thickness, including hinges, jamb, lock jamb, bead and if required base ties of 25x25x3mm angle, mild steel welded or rigidly fixed together by mechanical means with pressed door shutter using 70x30mm RMC section 5.84m @ 1.7 Kg/m, TataGalvano steel sheet embossed 85x196 cms and outer stiffeners 12x80 cms, 4 nos, including M.S. pressed butt hinges 2.5 mm thick with mortar guards, lock strike-plate and shock absorbers, SS aldrobs, SS tower bolts 2 nos and SS handles 2 nos as specified and applying a coat of approved steel primer after pre-treatment of the surface as directed by Engineer-in charge:	1.000	sqm	Rs	sqm
19	13.1.1 - Labour charge for 12 mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	1.000	sqm	Rs	sqm
20	13.16.1- Labour charge for 6 mm cement plaster of mix:1:3 (1 cement : 3 fine sand)	1.000	sqm	Rs	sqm
			TOTAL		



APPENDIX - B (Steel Fabrication works)					
1	9.48.2- Labour charge for Providing and fixing M.S. Grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete.Fixed to openings/ wooden frames with rawl plugs screws etc	1.000	kg	Rs	kg
2	50.10.2- Labour charge for Steel work for purlin/single section with G I pipes including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete	1.000	kg	Rs	kg
3	OD21364/2026-2027- Labour charge for fixing Poly carbonate single wall plain sheet 3 mm thick as approved by the Engineer in charge. The sheets shall be fixed using self drilling/ self tapping screw of size (5.5x55mm) with EPDM seal complete upto any pitch in horizontal /vertical / curved surface, but excluding the cost of purlins, rafters, trusses, and including cutting to size and shapes where ever required.	1.000	sqm	Rs	sqm
4	10.26.3- Labour charge for fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approves steel primer.G.I. pipes	1.000	kg	Rs	kg
5	10.28- Labour charge for fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.)	1.000	kg	Rs	kg
				TOTAL	

APPENDIX - C (Painting Works)					
1	13.43.1- Labour charge for Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface:Water thinnable cement primer	1.000	sqm	Rs	sqm
2	13.48.2- Labour charge for Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications:Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture	1.000	sqm	Rs	sqm
3	13.60.1- Labour charge for Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade:Two or more coats on new work	1.000	sqm	Rs	sqm
4	13.26 - Labour charge for Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	1.000	sqm	Rs	sqm
				TOTAL	

APPENDIX - D (Flooring Works)					
1	11.20.1 - Labour charge for Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete on 20 mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand).Light shade pigment using white cement	1.000	sqm	Rs	sqm
2	11.41.2 - Labour charge for laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4(1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete.Size of Tile 600 x 600 mm.)	1.000	sqm	Rs	sqm
3	OD21361/2026-2027 - Labour charge for fixing I st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer -in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.)	1.000	sqm	Rs	sqm
4	8.2.2.1 - Labour charge for fixing 18 mm thick gang saw cut, mirror, polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations, of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shadeArea of slab upto 0.50 sqm	1.000	sqm	Rs	sqm
				TOTAL	

APPENDIX - E (Aluminium Fabrication Works, Interior Works)					
1	21.1.1.2 - Labour charge for fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS : 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be	1.000	kg	Rs	kg
2	OD21362/2026-2027- Labour charge for fixing 4 mm thick ACP, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer - in- Charge.	1.000	sqm	Rs	sqm
3	21.3.1- Labour charge for fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer - in -Charge. (Cost of aluminium snap beading shall be paid in basic item):With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	1.000	sqm	Rs	sqm

DISTRICT NIC M ; 41 KENDRA
22 MAR
MALAPPURAM

4	9.119- Labour charge for fixing factory made P.V.C. door frame of size 50x47 mm with a wall thickness of 5 mm, made out of extruded 5 mm rigid PVC foam sheet, mitred at corners and joined with 2 Nos. of 150 mm long brackets of 15x15 mm M.S. square tube, the vertical door frame profiles to be reinforced with 19x19 mm M.S. square tube of 19 gauge, EPDM rubber gasket weather seal to be provided through out the frame. The door fame to be fixed to the wall using M.S. screws of 65/100 mm size, complete as per manufacturer's specification and direction of Engineer-in Charge.	1.000	metre	Rs	metre
5	9.120.1 - Labour charge for fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and sized of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, 70 mm width out of whicj 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5mm thick, 95 mm wide PVC sheet out of which75 mm shall be tapered in 45 degree on th inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mmx2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail. paneling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded /sealed to the styles & rails with 7 mm (5 mm + 2 mm) thick x 15 mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer -in-charge, manufacture's specification & drawing.20 mm thick plain PVC door shutters	1.000	sqm	Rs	sqm
6	9.160.1 - Labour charge for Providing and fixing skirting with pre-laminated medium density fibre board exterior grade (Grade-I) conforming to IS: 14587:1998 marked, with (one side decorative and other side balancing lamination and edges to be sealed with PVC edge bending tape 2.00 mm thick of approved brand with necessary fixing arrangements and screws, including drilling necessary holes for rawl plugs etc. all complete.18 mm thick.	1.000	sqm	Rs	sqm
7	50.9.12.1 - Labour charge for fixing Thomson Multi wood board or equivalent make, in shelves with screws and fittings wherever required, edges to be painted with polyurethane primer (fittings to be paid separately) as per the direction of site Engineer-in-charge.	1.000	sqm	Rs	sqm
8	9.115- Labour charge for fixing powder coated telescopic drawer channels 300 mm long with necessary screws etc. complete as per directions of Engineer -in-charge.	1.000	set	Rs	set
9	9.59.3- Labour charge for fixing ISI marked oxidised M.S. single acting spring hinges with necessary screws etc. complete. (Copper oxidized as per IS 1378).100mm	1.000	no	Rs	no
10	9.79.1- Labour charge for fixing special quality bright finished brass cupboard or ward robe locks with four levers of approved quality including necessary screws etc. complete.40 mm	1.000	no	Rs	no
11	9.81.2- Labour charge for fixing bright finished brass handles with screws etc. complete:100 mm	1.000	nos	Rs	nos
			TOTAL		

APPENDIX - F (Plumbing & Sanitation Works)					
1	2.8.1- Labour charge for Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds	1.000	cum	Rs	cum
2	OD21366/2026-2027- Labour charge for Filling with 6mm stone aggregate in trenches lead up to 50 m and lift up to 1.5 m as per direction of site Engineer-in-charge	1.000	cum	Rs	cum
3	51.2.4- Labour charge for Filling with Sand Supplying and filling sand in foundation trenches of culvert for stabilizing the top clay layer including watering, ramming, consolidating and dressing, etc complete for improving bearing capacity of soil.	1.000	cum	Rs	cum
4	50.6.2.1 - Labour charge for Solid block masonry using pre cast solid blocks (Factory made) of size 30x20x15 cm or nearest available size confirming to IS 2185 part I of 1979 for foundation and plinth with thickness 15cm in: CM 1:6 (1 cement :6 coarse sand) etc complete	1.000	cum	Rs	cum
5	5.36 - Labour charge for Providing and placing in position precast reinforced cement concrete waffle units, square or rectangular as per design and shape for floors and roofs in 1:11/2:3 (1 cement : 1 1/2 coarse sand : 3 graded stone aggregate 10 mm nominal size), including flush or deep ruled pointing at joints in cement mortar 1:2 (1 cement : 2 Fine sand), making necessary holes of required sizes for carrying through service lines etc., providing steel hooks for lifting etc, form work in precas ting, handling, hoisting, centering and erection complete for all floor levels but excluding the cost of reinforcement	1.000	cum	Rs	cum
6	5.22.6 - Labour charge for Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth levelThermo - Mechanically Treated bars of grade Fe-500D or more	1.000	kg	Rs	kg
7	51.19.ST4 - Labour charge for Supplying and installing ready made PVC Septic tank including the cost of carriage, trenching, placing at the level below ground level as specified as per the direction of engineer in charge (Provision for CC/RCC/Sand/06mm aggregate for the preparation of bed shall be paid separately) 4. 35 to 50 flush capacity	1.000	each	Rs	each
8	18.48 - Labour charge for Providing and placing on terrace (at all floor levels) polyethylene water storage tank :ISI 12701 marked, with cover and suitable locking arrangement and making	1.000	litre	Rs	litre

DISTRICT NIKSHAYA KENDRA
22 OCT
MALAPPURAM

9	17.3.1 - Labour charge for Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coup ling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :W.C. pan with ISI marked white solid plastic seat and lid.	1.000	each	Rs	each
10	17.7.4 - Labour charge for Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and	1.000	each	Rs	each
11	17.11.2 - Labour charge for Providing and fixing white vitreous china laboratory sink with C.I brackets, C.P. brass chain with rubber plug 40 mm C.P brass waste and 40 mm C.P. brass trap with necessary C.P. brass unions complete, including painting of fittings and brackets, cutting and making good the wall wherever required:Size 600x450x200 mm	1.000	each	Rs	each
12	OD21365/2026-2027 - Labour charge for Providing and fixing 15mm C.P brass pillar taps with elbow operated levers ISI marked	1.000	each	Rs	each
13	18.50.1 - Labour charge for Providing and fixing C.P brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms.15 mm nominal bore	1.000	each	Rs	each
14	18.58.2.1 - Labour charge for Providing and fixing PTMT grating of approved quality and colour. Rectangular type with openable circular lid150 mm nominal size square 100 mm diameter of the inner hinged round grating	1.000	each	Rs	each
15	50.17.1.5 - Labour charge for Supplying and fixing CP Health Faucet superior quality (Jagur or equvalent make) including cost of materials and labour charges etc complete as per the direction of site Engineer-in-charge	1.000	no	Rs	no
16	50.18.8.2.2 - Labour charge for Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Concealed work, including cutting chases and making good the wall etc. 20 mm pipe 10 Kgf/ cm2tc	1.000	metre	Rs	metre
17	50.18.8.3.2 - Labour charge for Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Concealed work, including cutting chases and making good the wall etc. 25 mm pipe 10kgf /cm2	1.000	metre	Rs	metre
18	50.18.8.4.1 - Labour charge for Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Concealed work, including cutting chases and making good the wall etc. 32 mm pipe 10Kgf/cm2	1.000	metre	Rs	metre

19	50.18.8.5.1 - Labour charge for Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. concealed work, including cutting chases and making good the wall etc. 40 mm pipe 10 kgf/ cm2	1.000	metre	Rs	metre
20	50.18.8.6.2 - Labour charge for Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Concealed work, including cutting chases and making good the wall etc. 50 mm pipe 6 kgf/cm2t	1.000	metre	Rs	metre
21	50.18.8.7.1 - Labour charge for Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Concealed work including cutting chases and making good the wall etc. 63 mm pipe 6 Kgf/cm2	1.000	metre	Rs	metre
22	50.18.8.9.1 - Labour charge for Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Concealed work, including cutting chased and making good the wall etc. 110 mm pipe 6kgf/cm2	1.000	metre	Rs	metre
23	50.18.9.12.2 - Labour charge for Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 20 mm dia 10Kgf/cm2 External work- Exposed on wall	1.000	metre	Rs	metre
24	50.18.9.13.2 - Labour charge for Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 25 mm dia 10 Kgf/cm2- External work - Exposed on wall	1.000	metre	Rs	metre
25	50.18.9.14.1 - Labour charge for Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 32 mm dia 10 Kgf/cm2 - External work- Exposed on wall Net Total 35.000metre @	1.000	metre	Rs	metre
26	50.18.9.15.1 - Labour charge for Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 40 mm dia 10Kgf/cm2- External work- Exposed on walle	1.000	metre	Rs	metre
27	50.18.9.6.2 - Labour charge for Providing and fixing PVC pipes includings jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 50 mm dia 6 Kgf/cm2	1.000	metre	Rs	metre

28	50.18.9.7.1 - Labour charge for Providing and fixing PVC pipes includings of pipes with one step PVC solvent cement, trenching refilling & testing of joints complete as per direction of Engineer in Charge. 63 mm dia 6Kgf/cm2	1.000	metre	Rs	metre
29	50.18.9.9.1 - Labour charge for Providing and fixing PVC pipes includings jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of Joints complete as per direction of engineer in charge.110 mm dia 6Kgf/cm2	1.000	metre	Rs	metre
			TOTAL		

Address of firm :

Signature :

Project manager cum Exe.secretary
District Nirmithi Kendra, Malappuram.

22/10/26

Signature :

Project Manager Cum
Executive Secretary
District Nirmithi Kendra
Civil Station, Malappuram